

**WHITE PARK - BOPARC  
CITY OF MORGANTOWN  
MORGANTOWN, WV**

ITEM NO.	DESCRIPTION	UNIT	EST QUANTITY	UNIT PRICE	EXTENDED PRICE
1	Mobilization/Demobilization	LS	1		
2	Demolition, Removal of Existing Playground Equipment	LS	1		
3	Demolition, Removal of Existing Trees, Clearing, Grubbing	SY	76		
4	Topsoil, Strip and Stockpile, Assume 6" Depth	CY	239		
5	Topsoil, Replacement, 4" Depth	CY	111		
6	Topsoil, Remove Excess	CY	128		
7	Excavation - Cut to Fill	CY	335		
8	Remove Excess Cut	CY	234		
9	Concrete Pavement, 4000 psi Fiber Reinforced, 4" Depth (Sidewalk)	SY	27		
10	Installation of Playground Equipment	LS	1		
11	Poured-in-Place Play Surface, 3.5" Depth (CFH=96")	SY	390		
12	Poured-in-Place Play Surface Subbase, 4" Depth	SY	390		
13	Poured-in-Place Play Surface Subbase Containment Border	LF	239		
14	Wood Border, 6"x6" Extreme Weather Treated	LF	245		
15	Install Furnished Mulch, 4" Depth	CY	10		
16	Weed Block Fabric, 20-yr, 5 oz. Professional Grade	SY	91		
17	4" Dia. Underdrain, Single-wall Wrapped in Geotextile	LF	354		
18	R-4 Riprap, 18" Placement Thickness	CY	11		
19	Rock Construction Entrance	EA	1		
20	Erosion Control Blanket, North American Green S75BN or Approved Equal	SY	703		
21	Seeding and Soil Supplements, KY-31 Tall Fescue	SY	1001		
22	8" Compost Filter Sock	LF	53		
23	12" Compost Filter Sock Check Dam	LF	39		
24	18" Compost Filter Sock	LF	38		
<b>TOTAL WHITE PLAYGROUND</b>					