

**WHITE PARK - BOPARC
CITY OF MORGANTOWN
MORGANTOWN, WV**

ITEM NO.	DESCRIPTION	UNIT	EST QUANTITY	UNIT PRICE	EXTENDED PRICE
1	Mobilization/Demobilization	LS	1		
2	Demolition, Removal of Existing Playground Equipment	LS	1		
3	Demolition, Removal of Existing Trees, Clearing, Grubbing	SY	76		
4	Topsoil, Strip and Stockpile, Assume 6" Depth	CY	199		
5	Topsoil, Replacement, 4" Depth	CY	122		
6	Topsoil, Remove Excess	CY	77		
7	Excavation - Cut to Fill	CY	204		
8	Remove Excess Cut	CY	204		
9	Concrete Pavement, 4000 psi Fiber Reinforced, 4" Depth (Sidewalk)	SY	27		
10	Installation of Playground Equipment	LS	1		
11	Poured-in-Place Play Surface, 3.875" Depth (CFH=96")	SY	390		
12	Poured-in-Place Play Surface Subbase, 4" Depth	SY	390		
13	Poured-in-Place Play Surface Concrete Containment Border	LF	239		
14	4" Dia. Underdrain, N-12 HDPE Storm Wrapped in Geotextile (Perforated)	LF	354		
15	R-4 Riprap, 18" Placement Thickness	CY	11		
16	Rock Construction Entance	EA	1		
17	Erosion Control Blanket, North American Green S75BN or Approved Equal	SY	688		
18	Seeding and Soil Supplements, KY-31 Tall Fescue	SY	1096		
19	8" Compost Filter Sock	LF	53		
20	12" Compost Filter Sock Check Dam	LF	39		
21	18" Compost Filter Sock	LF	38		
TOTAL WHITE PLAYGROUND					