

MARILLA PARK PLAYGROUND MEASUREMENT AND PAYMENT

#1- MOBILIZATION / DEMOBILIZATION

The cost for mobilization and demobilization shall be paid for by the lump sum bid price. The cost shall also include all necessary material for protecting existing sidewalks/curbs, etc. during vehicular crossing. The cost shall not exceed 5% of the total project bid.

#2- INSTALLATION OF THE PLAYGROUND EQUIPMENT

The cost for the installation of the playground equipment shall be paid for by the lump sum bid price. The cost shall also include installing foundations, erecting the equipment per equipment manufacturer's recommendations, and any minor grading of the existing stone to ensure positive drainage the drains. The playground equipment will be delivered to the site by the City and must be coordinated by the contractor. The playground equipment can only be installed by a certified contractor.

#3- POURED-IN-PLACE PLAY SURFACE (CFH=144")

The cost for the poured-in-play surface shall be paid for by the square yard bid price. The cost shall also include any necessary fine grading or prepping the existing stone subbase and adjusting the rim of the yard drains if necessary. The poured-in-place play surface shall be NO FAULT brand and installed by a certified contractor.

#4- POURED-IN-PLACE PLAY SURFACE SUBBASE CONTAINMENT BORDER

The cost for the poured-in-play surface subbase containment border shall be paid for by the linear foot bid price. The border shall consist of either concrete, HDPE, or hard plastic material. The bid item shall include all excavation, form work, anchoring, etc.

#5- VEGETATION RESTORATION

The cost for any restoration of existing vegetation shall be paid for by the lump sum bid price. The work shall include any fine grading, seeding and mulching necessary to establish vegetation in any disturbed by the installation of the playground.