

**BOPARC - KREPPS PARK TENNIS COURTS
CITY OF MORGANTOWN
MORGANTOWN, WV**

ITEM NO.	DESCRIPTION	UNIT	EST QUANTITY	UNIT PRICE	EXTENDED PRICE
1	Mobilization/Demobilization	LS	1		
2	Demolition & Disposal of Existing Court Surface	SF	1,750		
3	Demolition & Disposal of Existing Fence	LF	225		
4	Demolition & Disposal of Existing Tennis Nets (2), Basketball Hoops (2), & Trench Drains (2)	LS	1		
5	Silt Fence	LF	270		
6	Topsoil, Strip and Stockpile, Assume 6" Depth	CY	20		
7	Excavation of Streambank	CY	220		
8	Streambank Rip-Rap Armor	TN	100		
9	Ditch Lines	LF	165		
10	6" PVC Storm Pipe	LF	220		
11	Nyloplast Yard Inlets	EA	4		
12	Rock Outlet Protection	EA	1		
13	10-FT Tall Fencing (Exterior Fence & Between Basketball & Tennis Court)	LF	320		
14	4-FT Tall Fencing (Between Pickleball Courts & Tennis Court)	LF	115		
15	New Court Additions (Includes Grading, Separation Fabric, 8" of 1.5" Base Stone, & 3" of Base Asphalt)	SF	900		
16	Miscellaneous Repairs to Existing Court Surface (Cracks, Patches, etc.)	LS	1		
17	Resurfacing Existing Tennis Court Area	SF	9,550		
18	New Striping for Tennis Court	LF	525		
19	New Tennis Net (Install only)	EA	1		
20	New Striping for Pickleball Courts	LF	400		
21	New Pickleball Nets (Install only)	EA	2		
22	Resurfacing Existing Basketball Court Area	SF	3,100		
23	New Striping for Basketball Court	LF	300		
24	New Basketball Hoops (Install only)	EA	2		
25	Top Coat Sealer for All Courts	SF	13,550		
26	Park Benches (Install only)	EA	2		
TOTAL BID COST					