

**WILES HILL PLAYGROUND - BOPARC  
CITY OF MORGANTOWN  
MORGANTOWN, WV**

ITEM NO.	DESCRIPTION	UNIT	EST QUANTITY	UNIT PRICE	EXTENDED PRICE
1	Mobilization/Demobilization	LS	1		
2	Demolition, Removal of Existing Walls	LS	1		
3	Demolition, Removal of Existing Play Surface and Subbase	LS	1		
4	Topsoil, Strip and Stockpile, Assume 6" Depth	CY	18		
5	Topsoil, Replacement, 4" Depth	CY	24		
6	Excavation - Cut	CY	65		
7	Remove Excess Cut	CY	65		
8	Poured-in-Place Play Surface, 3.875" Depth (CFH=96")	SY	330		
9	Poured-in-Place Play Surface Subbase, 4" Depth	SY	330		
10	Poured-in-Place Play Surface Concrete Containment Border	LF	114		
11	8" Dia. N12 HDPE Storm (Solid)	LF	11		
12	4" Dia. Underdrain, N-12 HDPE Storm Wrapped in Geotextile (Perforated)	LF	171		
13	6" Dia. Underdrain, N-12 HDPE Storm Wrapped in Geotextile (Perforated)	LF	47		
14	8" Dia. N12 HDPE Storm End Section	EA	1		
15	12" Dia. Inline Yard Drain	EA	1		
16	R-3 Riprap, 9" Placement Thickness	CY	2		
17	Segmental Block Retaining Wall 1	SF	300		
18	Segmental Block Retaining Wall 2	SF	57		
19	Aluminum Fence	LF	24		
20	Erosion Control Blanket, North American Green S75BN or Approved Equal	SY	83		
21	Seeding and Soil Supplements, KY-31 Tall Fescue	SY	204		
22	12" Compost Filter Sock	LF	130		
<b>TOTAL WILES HILL PLAYGROUND</b>					